

REGIONAL INSTITUTE OF EDUCATION : BHUBANESWAR
CAMPUS & WELFARE SECTION

Quotation No:- 1241

Dated :- 23.3.16

Sub: Quotation for LAN work in DMS old Computer Lab and New Computer Lab-reg.

The Institute planned to do the LAN (Physical Networking) in DMS old Computer Lab and New Computer Lab. There will be 30 network ports in old Computer Lab and 30 network ports in New Computer lab. Detail specification and requirement of items are attached herewith for reference.

Interested suppliers/firms are requested to quote their rates itemwise and total cost inclusive of all Taxes. The firms may visit /inspect the site to ensure the quoted prices are realistic in terms of length of casing, cabling, capping etc. Valid PAN/TIN no may be mentioned in the quotations otherwise the quotation shall not be entertained. The quotation may be reached to the undersigned in a sealed cover superscribing "Quotation for LAN work in DMS " by registered post only on or before 04.04.2016 by 5.00pm. Late receive of quotations will not be entertained.

The Principal reserves the right to accept/reject any/all quotations without assigning any reason thereof. For further queries, if any please contact to Section Officer, C & W Section of the Institute.

Note : Special discount, if any, offered to Educational Institutions may also please be indicated.

This issues with approval of the Principal.


Administrative Officer

Copy to :-

1. I/C CAC with a request to upload in the institute website.
2. All notice board of the Institute/DMS/Hostels/Guest House

Regional Institute of Education, Bhubaneswar
Computer Application Centre

Date:.....

Detailed work plan & requirement of components in LAN (Physical networking) in DMS Old Computer Lab and New Computer Lab.

Total 30 network ports in Old Computer Lab and 30 network ports in New Computer Lab.

Sl No.	Item Make/Model	Specification	Quantity Required	Unit Price * (in Rs)	Total Price * (in Rs)
1	Cisco SG92-24	Fast Ethernet 10/100 Compact 24-Port Gigabit Switch Unmanaged - 2SFP Ports Rack-mountable aLL Gigabit LAN Switch+2 Mini-GBIC Slot	03 nos		
2	D-Link I/O box face plate	Dual D-Link CAT 6 I/O Set Face Plate with Gang Box	30 nos		
3	D-Link patch cord	D-Link 3 Meters (CAT 6)	60 nos		
4	Cable laying with casing & capping (Per Meter)	D-Link(CAT 6)	For 60 connections		
5	D-Link patch panel	24 port D-Link Patch Panel CAT 6 UTP 24 Port	03 nos		
6	D-Link patch cord	D-Link 1 Meter(CAT 6)	60 nos		
7	HCL 6u Wall Mount Network Rack Ibpws456u	Front Door with Toughened Glass quality. Adjustable Mounting rails - Front and Back 2 Fan Mounting provision Top and bottom cable entry provides Optimal flexibility for cable management Backside open with Easy wall mount provision Frame structure with max loading capacity up to 60kg.	01 no		
8	Installation charges				
Total:-					

* means rate inclusive of all taxes.

M.K. Mishra
18/03/16
(M.K. Mishra)

D.P. Mishra
18/03/16
(D.P. MISHRA)

[Signature]
18/03/16